BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT34110

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/19/2018-19, Date: 06.02.2019

Repair works to existing help point building and additional works at Hegadenagara in ward no 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PUTTARAJU A ( )		
				In Figures		In Words
1	39.27	Dismantling tiles and stacking the material within a radius of 50 meters,	Sqm	346.0	13587.42	Rupees Three Hundred Forty Six Only
2	144.6	Dismantling plastering and removing the debris with a lead upto 200m,	Sqm	24.0	3470.40	Rupees Twenty Four Only
3	8.9	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5000.0	44500.00	Rupees Five Thousand Only
4	32.97	Providing and fixing Special make glazed Vitrified tiles (Granomite finis) of approved make, quality and colour of sized 6000x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete.	Sqm	1000.0	32970.00	Rupees One Thousand Only
5	54.57	KSRB 15-3.7:- Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	258.0	14079.06	Rupees Two Hundred Fifty Eight Only
6	84.15	KSRB 15.3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	234.0	19691.10	Rupees Two Hundred Thirty Four Only
7	36.6	KSRB 15.3.13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	Sqm	204.0	7466.40	Rupees Two Hundred Four Only
8	36.6	KSRB 15.3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry and Concerte Surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	146.0	5343.60	Rupees One Hundred Forty Six Only
9	2.7	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications.	Cum	6300.0	17010.00	Rupees Six Thousand Three Hundred Only

Signature of the contractor

Executive Engineer

	pproved Qty.	Description	Unit	Approved Tender Rates of PUTTARAJU A ( )		
				In Figures		In Words
10	91.17	KSRB 15.15.3: Providing and applying painting in one coat with plastic emulsion paint of approved brand and manufacture on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, complete as per specifications. Page No.114/ Item No. 15.52 / PWD SR 2016-17	Sqm	47.0	4284.99	Rupees Forty Seven Only
11	84.15	SKSRB 15-16 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	89.0	7489.35	Rupees Eighty Nine Only
12	21	KSRB 7.15 : Providing, fabricating, assembling and fixing in position anodized aluminium partitions using aluminium sections of mat finish or glassy finish in combination of plain grove, single grove and double grove as per requirements for the frames of overall size 63.5mm x 38.1mm. with thickness of 2mm. having section weight, plain sections 1.05kg/m, single grove thickness 1.95mm. section weight 1.094kg/m, double grove thickness 1.9mm section weight 1.094kg/m and bottom member 114.3mm. x 44.45mm. thickness 3.18mm. weight 2.646 kg/m aluminium louvers section of size 36.5mm x 34.93mm 1.45mm. thick section weight 0.426kg/m; bottom portions provided with 12mm. thick pre-laminated sheet both sides of approved colour lamination exterior grade upto 0.9m height, spacing of vertical member not exceeding 0.6 m c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and riveted to the frames; the assembled frame stiffened with corner angles, stripped and fixed with screws, rawl Plugs and teak wood gutties to R.C.C. columns on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistelling and making good with cement mortar to match the surface; providing and fixing 5.5mm. thick plain glass for middle portion viz., 0.9mm to 2.13m. and top panel with louvers sections; the glass and panels fitted with glazing clips of 19mmx17.3mm of thickness 0.9mm. weight 0.124kg/m, aluminium sections treated for removal of any rust and prevention of further rust formation, coated with greasy materials for non-adherence of mortars or any other sticky materials; vertical members embedded in the flooring by making suitable sized holes and fixing with cement mortar, with necessary opening for fixing of door of standard sized (excluding cost of door) all the frame thoroughly cleaned, free from rust, scale or dirt including cost of materials, fixtures, labour and HOM of machinery -do- using aluminium section anodized to	Sqm	3695.0	77595.00	Rupees Three Thousand Six Hundred Ninety Five Only
13	1000	Supppying water storage tanks made of virgin polymer (LLDPE) with two layers outer black of blue and inner white layer of approved quality and make, conforming	No.	6.0	6000.00	Rupees Six Only
14	1	KSRB 11.11.3 : Providing and fixing white vitreous china clay, flat back wash basin of size 550x400mm with pair of 15mm C.P brass pillar taps with C.I./M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Unit	3770.0	3770.00	Rupees Three Thousand Seven Hundred Seventy Only
15	32.4	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shutterng machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Matirial 10cm thick RCC pre cast slab	Sqm	1800.0	58320.00	Rupees One Thousand Eight Hundred Only

Signature of the contractor

Executive Engineer

	pproved Qty.	Description	Unit	Approved Tender Rates of PUTTARAJU A ( )		
				In Figures		In Words
16	3	Supply of wooden writing table of size 4'X2' one side cupboard one drawer including cost of all lead and lift loading and unloading and all other incidental charges etc., complete as per specification and direction of the Engineer-in-charge of work	No.	12100.0	36300.00	Rupees Twelve Thousand One Hundred Only
17	2	Supply of High Back revolving chair with Arms bottom revolving base fixing moving wheels with seat and back cushion neatly finishing cost of all lead and lift loading and unloading and all other incidental charges etc.	No.	11000.0	22000.00	Rupees Eleven Thousand Only
18	2	Supply of visitor armed chair with seat and back cushion with seat and Rexion fixing standard size design no. D. 26# neatly finishing cost of all lead and lift loading and unloading and all other incidental charges etc.	No.	11250.0	22500.00	Rupees Eleven Thousand Two Hundred Fifty Only
19	30	Supply of good quality plastic chair (Nilkamal) including cost of all lead and lift loading and unloading and all other incidental charges complete as per specification and direction of the Engineer-in-charge of the work	No.	585.0	17550.00	Rupees Five Hundred Eighty Five Only
					413927.32	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92